BID DATE: May 7, 2008
TIME: 2:00 PM
PLACE: Sacramento, California
SPEC.#: 08-05
CONTR.#: C51369
BY: Lasarte

SUMMARY OF BIDS RECEIVED FOR
WELL REPLACEMENT
THERMALITO AFTERBAY DAM
STATE WATER FACILITIES
OROVILLE FIELD DIVISION
BUTTE COUNTY
CALIFORNIA

STATE OF CALIFORNIA
THE RESOURCES AGENCY
DEPARTMENT OF WATER RESOURCES

No. Addendums: 3

Item No.	Description	Quantity	Unit	ENGINEER'S ESTIMATE Unit Price	ENGINEER'S ESTIMATE Total	Hydro Resources Nevada Inc., DBA Humboldt Drilling & Pump Co. 4975 West Winnemucca Blvd. Winnemucca, NV 89445 775 623-5259 Unit Price	Total
1	Mobilization/Demobilization Of Drill Rig(s) and Equipment	1	EACH	LUMP SUM	$151,930.00	LUMP SUM	$296,000.00
2	Baker Tank Rental	7	EACH	$5,000.00	$35,000.00	$2,000.00	$14,000.00
3	Drilling 8-Inch Pilot Borehole	1,050	LF	$50.00	$52,500.00	$80.00	$84,000.00
4	Geophysical Survey	7	EACH	$3,500.00	$24,500.00	$4,500.00	$31,500.00
5	Ream 8-Inch Pilot Borehole To 32-Inch Borehole	910	LF	$135.00	$122,850.00	$250.00	$227,500.00
6	20-Inch O.D., 5/16-Inch Thick, Mild Steel Blank Casing	420	LF	$75.00	$31,500.00	$142.00	$59,640.00
7	20-Inch O.D., 304 Stainless Steel Wire Wrap Screen	420	LF	$350.00	$147,000.00	$365.00	$153,300.00
8	3-Inch Diameter, Mild Steel, Gravel Tube	280	LF	$12.00	$3,360.00	$19.15	$5,362.00
9	2-Inch Diameter, Mild Steel, Sounding Tube	840	LF	$8.00	$6,720.00	$15.00	$12,600.00
10	Filter Pack	77	CY	$220.00	$16,940.00	$400.00	$30,800.00
11	Bentonite Chip Buffer	35	LF	$120.00	$4,200.00	$200.00	$7,000.00
12	Sand-Cement Annular Seal	28	CY	$250.00	$7,000.00	$500.00	$14,000.00
13	Mechanical Well Development	42	HR	$350.00	$14,700.00	$750.00	$31,500.00
14	Installation And Removal Of Test Pump	7	EACH	$5,000.00	$35,000.00	$2,500.00	$17,500.00
15	Pumping Development	28	HR	$300.00	$8,400.00	$300.00	$8,400.00
16	Step-Drawdown Pump Test	42	HR	$200.00	$8,400.00	$300.00	$12,600.00
17	Constant-Discharge Test	84	HR	$200.00	$16,800.00	$300.00	$25,200.00
18	Pump Bowls, Column, Pump Motor, Strainer, Pedestal and Discharge Assembly	7	EACH	$35,000.00	$245,000.00	$48,563.00	$339,941.00
19	Pump Motor Control And Disconnect Panels, and Wiring	7	EACH	$15,000.00	$105,000.00	$15,000.00	$105,000.00
20	Decommissioning Well	7	EACH	$10,000.00	$70,000.00	$15,000.00	$105,000.00
21	Standby Time	56	HR	$325.00	$18,200.00	$250.00	$14,000.00
	Total				$1,125,000.00		$1,594,843.00

Guarantee TEN PERCENT (10%) OF THE AMOUNT BID

Surety Arch Insurance Company

Comments X Denotes corrected figure

AWARDED: MAY 13, 2008